

(30) Priority Data: 970970

WORLD INTELLECTUAL PROPERTY ORGANIZATION International Bureau



INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

51) International Patent Classification 6:

B66B 19/00

A1

(11) International Publication Number: WO 98/40303

(43) International Publication Date: 17 September 1998 (17.09.98)

FI

(21) International Application Number: PCT/FI98/00205

(22) International Filing Date: 6 March 1998 (06.03.98)

(71) Applicant (for all designated States except US): KONE OYJ [FI/FI]; Munkkiniemen puistotie 25, FIN-00330 Helsinki

7 March 1997 (07.03.97)

[FI/FI]; Munkkiniemen puistotie 25, FIN-00330 Helsinki (FI).


(72) Inventors; and
(75) Inventors/Applicants (for US only): PETTERSSON, Håkan [SE/SE]; Klippgatan 12 A, S-171 46 Solna (SE). VAN DER MEIJDEN, Gert [NL/NL]; Arnhemsweg 84, NL-6731 BV Otterlo (NL).

(74) Agent: KONE OYJ; Patent Dept., P.O. Box 677, FIN-05801 Hyvinkää (FI). (81) Designated States: AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CU, CZ, DE, DK, EE, ES, FI, GB, GE, GH, GM, GW, HU, ID, IL, IS, IP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, UA, UG, US, UZ, VN, YU, ZW, ARIPO patent (GH, GM, KE, LS, MW, SD, SZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, ML, MR, NE, SN, TD, TG).

Published

With international search report.

(54) Title: PROCEDURE AND APPARATUS FOR THE INSTALLATION OF AN ELEVATOR



(57) Abstract

On the second department of the second second

The invention relates to a procedure and an apparatus for plumbing and installing the shaft equipment for an elevator. A plumbing jig (22) is mounted in the upper part of the elevator shaft from the top floor (11), plumb lines (43) are attached to the plumbing jig from he top floor (11) and, using the plumb lines (43) attached to the plumbing jig (22), the shaft equipment (28) is positioned, whereupon the haft equipment (28) is fixed in place. The apparatus of the invention comprises supporting elements (41) that can be fixed to the elevator shaft, a plumbing jig (22) that can be attached to the supporting elements (41) and mounted substantially from the top floor (11), and plumb lines (43) that can be suspended from the plumbing jig (22) and extend into the elevator shaft (2) below the plumbing jig.

BEST AVAILABLE COPY

FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
ΑT	Austria	FR	France	LU	Luxembourg	SN	Senegal .
ΑU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
ΑZ	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgium	GN	Guinea	MK	The former Yugoslav	TM	Turkmenistan
BF	Burkina Faso	GR	Greece		Republic of Macedonia	TR	Turkey
BG	Bulgaria	HU	Hungary	ML	Mali	TT	Trinidad and Tobago
BJ	Benin	IE	Ireland	MN	Mongolia	UA	Ukraine
BR	Brazil	IL	Israel	MR	Mauritania	UG	Uganda
BY	Belarus	IS	Iceland	MW	Malawi	US	United States of America
CA	Canada	ΙT	Italy	MX	Mexico	UZ	Uzbekistan
CF	Central African Republic	JР	Japan	NE	Niger	VN	Viet Nam
CG	Congo	KE	Kenya	NL	Netherlands	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NO	Norway	ZW	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's	NZ	New Zealand		
CM	Cameroon		Republic of Korea	PL	Poland		
CN	China	KR	Republic of Korea	PT	Portugal		
CU	Cuba	KZ	Kazakstan	RO	Romania		
CZ	Czech Republic	LC	Saint Lucia	RU	Russian Federation		
DE	Germany	LI	Liechtenstein	SD	Sudan		
DK	Denmark	LK	Sri Lanka	SE	Sweden		
EE	Estonia	LR	Liberia	SG	Singaporc		
į							

WO 98/40303 PCT/FI98/00205

PROCEDURE AND APPARATUS FOR THE INSTALLATION OF AN ELEVATOR

The present invention relates to a procedure as defined in the preamble of claim 1 and to an apparatus as defined in the preamble of claim 10 for use in the installation of an elevator.

For trouble-free operation of an elevator, it is necessary that the elevator should run along a vertical line. The elevator is normally installed in an elevator shaft built from concrete. The guide rails for the elevator car and counterweight are fixed to the shaft walls using rail fixtures. During the installation of the elevator, the guide rails and other shaft equipment are adjusted to their proper positions. In this context, shaft equipment refers to guide rails, landing doors and their mounting brackets. In the vertical direction, the alignment is effected using plumb lines, which are fixed at a point above the shaft equipment to be installed in the elevator shaft and which extend through the whole length of the shaft. It has also been suggested that the alignment 20 could be done using a laser beam, but this method has not gained ground due to the costs and the difficult conditions at the site of installation.

In prior art, the plumb lines are fixed to the floor of a machine room above the shaft and so positioned that they can be used to align the shaft equipment, such as guide rails, and the landing doors. The ceiling of the elevator shaft must be provided with holes for the plumb lines.

30

35

The object of the present invention is to develop a new solution for plumbing the shaft equipment in an elevator shaft to their proper positions, a solution that does not require any communication with a space above the shaft and that can be implemented without working above the finished building. To achieve this, the procedure of the invention is characterised

by the features presented in the characterisation part of claim 1. The apparatus of the invention is characterised by the features presented in the characterisation part of claim 10. The features of certain other preferred embodiments are defined in the sub-claims.

5

10

15

20

25

30

When the solution of the invention is used, all the operations required in elevator installation can be carried out from the elevator shaft or from a landing. When trimming the plumbing jig, the installers can work from a landing, so no scaffolding or temporary erecting stages are needed. The job can be performed substantially faster than before, when it was necessary to build a scaffolding for work in the elevator shaft or when the work was done from the roof and a passage to the roof had to be provided in addition to a separate connection between the elevator shaft and the space above the shaft. Now, there is no need for elevator installers to go to the roof at any stage, so this allows a clear distinction to be made between elevator installation and other construction work. In the case of an elevator without machine room, the installers can directly communicate with each other throughout the installation process.

By using the solution of the invention, the plumbing of all shaft equipment, guide rails and landing door mounting brackets can be effected with four plumb lines when a gauge is used to position the guide rails for the counterweight. This also contributes towards faster installation and, by using a suitable gauge, the guide rails can be installed so that their guide surfaces will be in correct positions relative to each other.

A frame used for the plumbing, i.e. a plumbing jig, fixes the positions of shaft equipment at their proper locations in the vertical direction. When the plumbing jig is moved horizontally during fine adjustment at the final plumbing stage, the

WO 98/40303 PCT/FI98/00205

various pieces of shaft equipment of the elevator remain in correct positions relative to each other. Thus, if the position of one of the plumb lines has to be readjusted, this can be done without separately readjusting the other plumb lines.

5

In the following, the invention will be described in detail the aid of some of its preferred embodiments by referring to the attached drawings, in which

- 10 Fig. 1 presents an elevator shaft in lateral view,
 - Fig. 2 presents a plumbing jig in top view,
- Fig. 3 presents an arrangement according to the invention in lateral view,
 - Fig. 4 presents another arrangement according to the invention in lateral view,
- 20 Fig. 5 presents a third arrangement according to the invention in lateral view,
 - Fig. 6 presents a fourth arrangement according to the invention in lateral view,

25

- Fig. 7 presents a fourth arrangement according to the invention viewed from the top floor.
- Fig. 1 presents a cross-section of an elevator shaft 2 in side view. The shaft comprises a back wall 4 and a front wall 6, the latter being provided with door openings 8 at the landings 10 and 11, and side walls 12. The shaft extends somewhat below the lowest floor, forming a pit 20 in which the shaft equipment needed below the elevator car is installed. At the top, the shaft is delimited by the ceiling 16 of the shaft. The door openings are provided with temporary

WO 98/40303 PCT/F198/00205

safety walls 18, which may consist of e.g. plastic plates, wooden beams or steel bars. According to a first alternative embodiment of the invention, the shaft is provided with supporting elements 14 fixed to the side walls of the shaft above the top floor 11, on which elements the plumbing jigs 22 can be mounted as described below in detail.

10

15

20

25

30

35

The plumbing jig 22 (Fig. 2) is mounted using telescopic tubes 24 placed on the supporting elements 14, the tubes being adjusted to a length corresponding to the shaft width. The telescopic tubes 24 are attached to profiled bars comprised in the supporting elements 14. When the supporting elements 14 and the tubes 22 are mounted, their straightness is verified by means of a spirit level. The plumbing jig consists of two side bars 26 which, in the depth direction of the shaft, extend from the shaft door toward the back wall of the shaft to the plane of the guide rails 28. Fixed to the door-side ends of the side bars 26 are square elbows 30, which are further attached to a front bar 32 connecting the square elbows 30 to each other. The square elbows are adjustably attached to the side bars and the front bar, allowing the same mounting jig to be used in elevator shafts of different dimensions. Attached to the front bar is a plumbing plate 34, which is provided with notches 36 located at the positions where the plumb lines for the landing door mounting brackets are to be set. Notches 36' and 36'' are for different elevators. Attached to the shaft-side ends of the side bars are plumbing plates 38 for the guide rails of the elevator car, the plates being provided with notches 40 for the plumb lines 43 used to plumb the guide rails 28. The attachment of the plumbing plates 38 to the side bars 26 can be adjusted according to the dimensions of the elevator shaft. Once the plumbing jig has been assembled according to the dimensions of the elevator to be installed, their mutual positions will remain unchanged. Turning or rotating the plumbing jig horizontally causes a corresponding change in the posiTo carry out the plumbing, a plumbing jig assembly corresponding to the configuration of the elevator shaft is set up. The plumb lines are dropped into the shaft and fixed to the positions marked on the plumbing plates. On the shaft bottom, the positions of the guide rail lines are measured correspondingly and the plumb lines are fixed in place. At each floor, the plumb lines and the corresponding positions of guide rails and landing door mounting brackets are checked. If necessary, the plumb line positions are readjusted to bring the entire shaft into alignment. Installation of the elevator guide rails is started from the lowest guide rail, proceeding one guide rail pair at a time up to the top. The positions of the counterweight guide rails are determined by means of a special gauge 60, which is used to ensure that the guide rails are installed in a straight vertical line and also that the guide rail guide surfaces are perpendicular and in alignment with the guide surfaces of other guide rails. The gauge comprises a bar 62 placed between the guide rails in the shaft and provided with aligning points for a plumb line 43, and a rod 64 between the counterweight guide rails 67 and 68 and a rod 66 between one 68 of the counterweight guide rails and one 28 of the car guide rails.

25

30

35

10

15

20

Figures 3, 4 and 5 illustrate different arrangements for mounting the supporting elements for the plumbing jig in the elevator shaft. In Fig. 3, a supporting element has been fixed to a shaft wall. The supporting element consists of a horizontal bar 41 whose one end is fastened to an adapter plate 42 bolted to the wall while the other end rests on an oblique supporting bar 44. The supporting bar is attached by its lower end to another adapter plate 46. When the supporting element is being mounted, the adapter plates are used to adjust the supporting element so as to bring it into a horizontal position and into alignment with another supporting

and the control of th

WO 98/40303 PCT/FI98/00205

element mounted on the opposite shaft wall. The adapter plates are placed on the shaft wall adjoining the landing, so the supporting elements are easily accessible and adjustable during installation. The supporting element is preferably mounted above the top floor so that it is at a suitable height for installers working on the floor and that the fixtures for all guide rails can be easily positioned by means of the plumb lines 43. The plumbing jig 22 is placed on and attached to the supporting elements.

10

15

20

25

694355

In the embodiment illustrated by Fig. 4, the supporting element 48 is mounted on the top floor 11, being fixed to the landing floor 50 e.g. by means of bolts 52. Alternatively, the supporting element may be fixed to other landing structures. The plumbing jig 22 itself may be implemented as described above.

In a further embodiment (Fig. 5) of the invention, the supporting elements for the plumbing jig are formed from two bars 54 suspended from the ceiling 16 of the elevator shaft. The bars 54 are fixed to wire cables or bars 56 whose other ends are fixed to hooks 58 mounted in the shaft ceiling. The vertical position of the supporting elements is adjusted e.g. by means of an adjusting screw fitted at the lower end of bar 56. In this case, the supporting element is preferably placed at a suitable working height relative to the top floor. The plumbing jig 22 may be implemented as described above.

In the fourth embodiment to install the plumbing jig (Fig. 6 and Fig. 7) there are mounting brackets 62, which are fixed to the door jambs 60 on the top floor 11. The brackets may also be fixed to the side walls if there is no front wall or they may be fixed to the edges of the front wall on the both sides of the door openings 8. According to this embodiment the plumbing jig 22 can be fixed easily and the mounter does not need to stretch himself to the shaft when fixing the

plumbing jig.

In the foregoing, the invention has been described by the aid of one of its embodiments. However, the presentation is not be regarded as constituting a restriction of the sphere of patent protection, but the embodiments of the invention may be varied within the limits defined by the following claims.

A control of the second of the

CLAIMS

- 1. Procedure for positioning and mounting the shaft equipment (28) to be installed in an elevator shaft (2), in which procedure the various pieces of shaft equipment (28) are positioned using plumb lines (43) attached to a plumbing jig (22) and fixed in place after the positioning, characterised in that
- the plumbing jig (22) is mounted in the upper part of the elevator shaft (2) working on the top floor (11),
 - the plumb lines (43) are attached to the plumbing jig (22) working on the top floor (11).
- 2. Procedure as defined in claim 1, characterised in that the plumbing jig (22) is mounted on a carrier (54) suspended from the ceiling (16), said carrier (54) being mounted in place from the top floor (11).
- 3. Procedure as defined in claim 1, characterised 20 in that the plumbing jig (22) is mounted on a carrier (48) fixed to the landing (50) of the top floor (11).
- Procedure as defined in claim 1, characterised in that the plumbing jig (22) is mounted on supporting elements (41,42) attached to the walls (12) of the elevator shaft.
- 5. Procedure as defined in any one of claims 1, characterised in that the plumbing jig (22) is mounted to the jambs of the top floor door or to the structure of the front wall of the top floor
- 6. Procedure as defined in any one of claims 1 5, characterised in that the plumbing jig (22) is mounted above the top floor (11).

7. Procedure as defined in any one of claims 1 - 6, char-acterised in that the shaft equipment (28) is positioned using a plumb line (43) and a gauge (62,66,67) placed between the plumb line (43) and the shaft equipment.

5

8. Procedure as defined in any one of claims 1 - 7, char-acterised in that, to install shaft equipment (28), the shaft equipment is lifted from the bottom of the shaft (20) using the elevator car.

10

9. Procedure as defined in any one of claims 1 - 8, char-acterised in that the plumbing jig is mounted and the plumb lines are positioned into the shaft without any scaffolds or ladders.

15

10. Apparatus for the plumbing and installation of shaft equipment for an elevator, characterised in that the apparatus comprises supporting elements (41;48;54) that is fixable to the elevator shaft (2), a plumbing jig (22) that is attachable to the supporting elements (41;48;54) and mountable substantially from the top floor (11), and plumb lines (43) that are suspendable from the plumbing jig and that extend into the elevator shaft (2) below the plumbing jig (22) and are used to align at least one guide rail.

25

11. Apparatus as defined in claim 10, characterised in that the supporting elements (41;48;54) are fixable to the shaft walls (12), to a floor (11), to the shaft ceiling (16) or to the door jambs

30

Villa Translation

12. Apparatus as defined in claim 10 or 11, characterised in that it comprises four plumb lines (43) and a gauge (62,66,67).






Fig. 1

अंदुबर्ग्स








Fig. 4





Fig. 5






Fig. 7

INTERNATIONAL SEARCH REPORT

International application No.

PCT	/FT	98/	'n	02	05
	,,,	201	v	~	\mathbf{u}

A. CLASSIFICATION OF SUBJECT MATTER					
IPC6: B66B 19/00 According to International Patent Classification (IPC) or to both national classification and IPC					
B. FIELD	S SEARCHED				
Minimum de	ocumentation searched (classification system followed by	classification symbols)	ļ		
IPC6: E					
Documentat	ion searched other than minimum documentation to the	extent that such documents are included in	the fields searched		
SE,DK,F	FI,NO classes as above				
Electronic d	ata base consulted during the international search (name	of data hase and, where practicable, search	terms used)		
WPI, PA	AJ	·	·		
	MENTS CONSIDERED TO BE RELEVANT				
Category*	Citation of document, with indication, where app	ropriate, of the relevant passages	Relevant to claim No.		
X	GB 2194984 A (OTIS ELEVATOR COMP 23 March 1988 (23.03.88), pa line 64 - line 66, figures	10-12			
A			1,4,6		
.,			2,1,0		
Х	PAJ, JP6009173, MITSUBISHI ELECT "Upper art template device f 940118, figure 3		10,11		
A			1,4		
					
A	US 5065843 A (D. RICHARDS), 19 N (19.11.91), column 4, line 3		1,6,9,10,11		
		·			
X Further documents are listed in the continuation of Box C. X See patent family annex.					
* Special categories of cited documents: "A" document defining the general state of the art which is not considered to be of national articles and not in conflict with the application but cited to understand the principle or theory underlying the invention					
"E" erlier d	"E" criter document but published on or after the international filing date "X" document of particular relevance: the claimed invention cannot be				
cited to	1." document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other profile received to the considered to involve an inventive step when the document is taken alone				
"P" document published prior to the international filing date but later than being obvious to a person skilled in the art					
the priority date claimed "&" document member of the same patent family Date of the actual completion of the international search Date of mailing of the international search report					
]	2.5 -06- 1998				
12 June 1998 Name and mailing address of the ISA/ Authorized officer					
Swedish Patent Office					
Box 5055	S, S-102 42 STOCKHOLM	Mariana Eddin			

Form PCT/ISA/210 (second sheet) (July 1992)

2

INTERNATIONAL SEARCH REPORT

-International application No.
PCT/FI 98/00205

C (Continuation). DOCUMENTS CONSIDERED TO BE RELEVANT				
Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.		
A	PAJ, JP 5186160, MITSUBISHI ELECTRIC CORP: "Elivator centring device", 930727, figure 2			
	TELL IN CONTINUATION OF SECOND SHOOT (2017 1 272)			

INTERNATIONAL SEARCH REPORT

Information on patent family members

29/04/98

International application No.

PCT/FI 98/00205

Patent document cited in search report	Publication date		Patent family member(s)	Publication date
GB 2194984 A	23/03/88	AU	585172 B	08/06/89
		AU	7820887 A	17/03/88
		CA	1279466 A	29/01/91
		CH	676114 A	14/12/90
.•	·	DE	3721930 A	24/03/88
		FI	85577 B	31/01/92
		FI	873385 A	12/03/88
		FR	2603876 A,B	18/03/88
		JP	2077574 C	09/08/96
		JP	7115817 B	13/12/95
		JP	63071091 A	31/03/88
		US	4819403 A	11/04/89
US 5065843 A	19/11/91	CN	1033571 B	18/12/96
		CN	1056471 A	27/11/91
		DE	69107509 D,T	18/01/96
		EP	0457152 A.B	21/11/91
		ES	2071155 T	16/06/95
		JP	2059507 C	10/06/96
		JP	5085681 A	06/04/93
		JP	7100582 B	01/11/95
		RU	2058928 C	27/04/96

This Page is Inserted by IFW Indexing and Scanning Operations and is not part of the Official Record

BEST AVAILABLE IMAGES

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images include but are not limited to the items checked:

⅓ BLACK BORDERS
M IMAGE CUT OFF AT TOP, BOTTOM OR SIDES
☑ FADED TEXT OR DRAWING
☐ BLURRED OR ILLEGIBLE TEXT OR DRAWING
☐ SKEWED/SLANTED IMAGES
COLOR OR BLACK AND WHITE PHOTOGRAPHS
☐ GRAY SCALE DOCUMENTS
☐ LINES OR MARKS ON ORIGINAL DOCUMENT
☐ REFERENCE(S) OR EXHIBIT(S) SUBMITTED ARE POOR QUALITY
OTHER:

IMAGES ARE BEST AVAILABLE COPY.

As rescanning these documents will not correct the image problems checked, please do not report these problems to the IFW Image Problem Mailbox.